

HIGH VOLTAGE AC TEST APPARATUS



Features

- Operating voltage 230V AC or 415 $\pm 10\%$, 50Hz
- Option of Manual or motorized control
- KV meter & Leakage current meter
- Tripping Current setting 50 & 100% of Rating with option of customized trip current setting
- **Option : Digital presetable count down timer 99.9 minutes with toggle switch for using or bypassing timer**
- 2 pole toggle switch or MCB for ON/OFF operation
- Indicating lamps for mains ON and HV ON
- Accuracy: $\pm 5\%$.
- **Option: $\pm 1\%$ & $\pm 3\%$.**
- **Automatic Test with Test Pass /Failure Indication suitable for Accessories and Appliances to do 3 to 5 Samples at a time for Range upto 3KVAC.**
- **Range: 3 to 30KVAC/50mA to 5A or as per Customers requirement & specification.**
- **Note: Also Available HVAC & DC in a Single Combo Unit with HVAC or HVDC Selector Switch.**